

**STATE OF OHIO
DEPARTMENT OF TRANSPORTATION**

**SUPPLEMENT 1063
SIGNAL CONSTRUCTION PERSONNEL REQUIREMENTS
(631, 632, 633)**

April 19, 2002

1063.01 Description

1063.02 Signal Construction Personnel Requirements

1063.01 Description. This supplement describes the requirements for the Contractor's supervisors and signal technicians on projects with Items 631 (sign flasher assembly, school speed limit sign assembly, and timer with enclosure), 632, and 633.

1063.02 Signal Construction Personnel Requirements. The Contractor shall assign a supervisor for this project. The supervisor shall be a full-time employee of the Contractor. The Contractor shall not change a supervisor assigned to a project without prior written notice.

All controller work as defined in items (1) through (4) shall be performed by an International Municipal Signal Association (IMSA) level two certified technician: (1) back panel wiring terminations; (2) programming; (3) turn on; and, (4) troubleshooting.

The Contractor shall also have a foreman assigned to each crew performing work for this project. A foreman shall be present at all times when work is performed by the crew. Each foreman shall be an IMSA level one certified technician. Prior verbal notice shall be provided to the Engineer by the Contractor in order to replace a crew foreman.

In addition, crafts people performing work as defined in items (5) through (11) shall be performed by an IMSA level one certified technician: (5) cable splices; (6) signal head installation; (7) cable and wire installation; (8) power service installation; (9) ground rod testing; (10) cable insulation testing; and, (11) field wiring terminations.

The Contractor shall present to the Engineer, prior to the commencement of work, the IMSA level one and two certification papers for all signal technicians working on this project.