

# Ohio Department of Transportation

## Prebid Questions

Project No. 091064

Sale Date - 7/15/2009

Question Submitted: 7/7/2009

Question Number: 1

Item 15, truncated domes, If these are glue downs on existing walk why is there orange fence and why do some have curb removal and no replacement and why is this done after pavement planing if ramp elevations are not changing?

**The construction fence will still be necessary to keep pedestrians out of the area while the work is being done. The curb directly in front of the walk is to be removed at the locations specified to make the walk traversable. The area of the removed curb will be covered with asphalt when the approach roadway is paved. The pavement planing is required to be completed first to avoid damaging the new truncated domes.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.