

Ohio Department of Transportation

Prebid Questions

Project No. 050155

Sale Date - 3/9/2005

Question Submitted: 2/25/2005

Question Number: 1

Pavement calculations on Plan Sheet 6 calls for 1329 cy of embankment. Since pavement grades do not change, where is there an embankment requirement?

This was an estimated quantity to provide material for finish grading adjacent to all placed concrete pavement.

Question Submitted: 3/4/2005

Question Number: 2

Regarding the Maintenance of Traffic note on Plan Sheet 2, there appears to be a conflict. The first paragraph states ODOT will erect barricades and the second paragraph states the contractor will perform this work. Who is responsible for closing the the weigh station?

ODOT will erect the barricades and the contractor shall maintain them thru-out the project. ODOT will remove the barricades at the end of the project.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.