

Ohio Department of Transportation

Prebid Questions

Project No. 070356

Sale Date - 8/1/2007

Question Submitted: 6/27/2007

Question Number: 1

Reinforcing for the approach slabs are usually included in item 526. It is included under item 509. Please verify.

Question Submitted: 6/29/2007

Question Number: 2

Item 516E31300Please review Page 45/76Joint Width seems to be incorrect.Please verify correct width.

Question Submitted: 7/16/2007

Question Number: 3

Where are the intermediate diaphragms on Structure COL-154-0413 to be paid?

Question Submitted: 7/16/2007

Question Number: 4

Where are the intermediate diaphragms on Structure COL-154-0413 to be paid?

Question Submitted: 7/16/2007

Question Number: 5

We submitted our question in June, with no reply.Letting is 7/18/07, we cannot submit our quote.The joint dimension on this project is incorrect.THE WIDTH IS WRONG.

Question Submitted: 7/5/2007

Question Number: 6

ref 108 approach slab weights are incorrect. Sheets 68 & 70/76the bottom bar marks AS501,502,503 & 504 quantities were missed(22 each).Also the weights for the marks AS1001,1002,1003 & 1004 are incorrect. Please verify.

Question Submitted: 7/6/2007

Question Number: 7

Typically on half width bridge projects, the bridge deck grooving is done after Phase II/closure pour is complete. Will this be the case on Bridge No. COL-154-0413?

Yes, the bridge deck grooving should be done after Phase 2/closure pour is complete.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.