

# Ohio Department of Transportation

## Prebid Questions

Project No. 100019

Sale Date - 1/14/2010

Question Submitted: 1/11/2010

Question Number: 1

Expansion joint details show VES-LMC be place in the joints monolithic with the overlay. No APP notes detail how the concrete in the joints below the plan specified thickness of the overlay is paid. No APP note pays for the material as incidental to item 516 'Str Stl Exp Jt'. Is the contractor to assume that this material will be paid under item 530 'Variable Thickness, Material Only'? Please verify.

**Plan sheet 14/29 addresses this question in paragraph 6 of the middle column – It will be paid as Item Structure Misc: VES-LMC Concrete Overlay (Variable Thickness) Material Only.**

Question Submitted: 1/8/2010

Question Number: 2

Can through traffic on EB 70 be detoured per sheets 5-7 more than one time provide the closure does not exceed 4 calendar days?

**No, the intent of the plans was to disrupt traffic with the full closure of eastbound 70 only one time for completion of this work. The notes are clear. The first gives a period not to exceed 4 calendar days... The second allows overlay repairs while maintaining traffic in one lane during allowable hours.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.