

# Ohio Department of Transportation

## Prebid Questions

Project No. 095008

Sale Date - 9/16/2009

Question Submitted: 9/14/2009

Question Number: 1

This question has to do with the Jacking and Temporary Support for both of the bridges on this job. On Bridge #MAR-231-0343 there is a lane closure set up on top of the bridge with temporary traffic signaling. If we perform our temporary support from the top of the bridge, will there be portable concrete barrier requirements or will the existing drums be good enough? On Bridge #FRA-710-0376, if we install our temporary support on the existing berm of the bridge, will portable concrete barrier be required? If PCB are required, can you specify a length for each bridge?

Question Submitted: 9/15/2009

Question Number: 2

The completion date for this project is 11/30/09. The bridge in Franklin County can only be worked at night from 10:00 pm to 5:00 am. The painting and epoxy injection are the two last things that will be done to complete the work. There is not enough time to put up heat enclosures to get the temperature requirements which will be needed in order to do the work and be off of the road by 5:00 am. This painting and epoxy injection will take place at night and in November. There is no way we are going to get the temperature requirements at night in November, and there is not enough time to put up heat enclosures. Can the painting and epoxy injection for this job be completed after the winter is over?

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.