

# Ohio Department of Transportation

## Prebid Questions

Project No. 070541

Sale Date - 12/19/2007

Question Submitted: 12/4/2007

Question Number: 1

There is a detail in the plans for each culvert showing low strength mortar backfill to the top of each culvert. Normaly this is only used under the pavement area. Are we to figure using LSM for the entire length? The plans do not tell or show any limits.

**Low strength mortar backfill need only be placed within the limits of the pavement including the paved berm as shown in the typical sections. Backfill beyond these limits shall be as per 603.10 and 603.11. Payment for backfill shall be included with item 603.**

Question Submitted: 12/4/2007

Question Number: 2

Item 54: Work Zone Marking Signs has a quantity of 108 each. Does this quantity include signs being used for the Detour?

**The signs for the detour are included.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.