

Ohio Department of Transportation

Prebid Questions

Project No. 090099

Sale Date - 2/4/2009

Question Submitted: 2/9/2009

Question Number: 1

1.) Item #33 Low Strength Mortar Backfill Plan quantity is estimated low for actual dimension Plan = 75 CY
Calculated = 115 CY Is an addendum needed for this item? 2.) Item #49 Epoxy Coated Reinforcing Steel No
quantity is shown for HW 1.1 headwalls on Culvert GEA-168-3.06 95 pounds is shown for HW 2.1 headwall for Culvert
GEA- 608-1.19 Culvert GEA-168-3.06 needs 2300 pounds Is an addendum needed for this item?

A1) The calculated quantity for the LSM is correct. The intent is to use the LSM only under the pavement to allow for quick pavement repair. Outside the pavement limits the intent is to use normal 603.10 backfill. A2) For GEA-168-3.06, the reinforcing is included for payment under Item 602 - Concrete Masonry as indicated on standard drawing HW-1.1.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.