

Ohio Department of Transportation

Prebid Questions

Project No. 080565

Sale Date - 10/8/2008

Question Submitted: 11/4/2008

Question Number: 1

The project has a pays items for Work Involving Non-Regulated Materials and Petroleum Contaminated Soil. The plan notes on sheet 11 do not mention existing tank removals. Plan sheet 44 shows the gas tanks. Has the tanks been previously removed or are these pay items to include the removal?

There are not any underground tanks intended to be removed on this project or under this pay item. These pay items are for "Soil Excavation Adjacent to the Gas Station," as stated in notes on sheet 11.

Question Submitted: 11/5/2008

Question Number: 2

Page 10 of the plans includes a note for an Interim Completion Date. It is our understanding this note would no longer be included in projects. Should the interim completion date note be removed?

Question Submitted: 11/5/2008

Question Number: 3

On plan page 89E, the plans detail a proposed 8" watermain to be installed on centerline of Seven Hills Drive. Existing Seven Hills drive is only approx 20' wide. Plan note on sheet 14 indicates that traffic must be maintained on all side roads except where noted. Seven Hill Drive is not noted. It will be extremely difficult to maintain traffic on Seven Hills Drive while the waterline is being installed. Please review

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.

Ohio Department of Transportation

Prebid Questions

Project No. 080166

Sale Date - 3/26/2008

Question Submitted: 2/28/2008

Question Number: 1

Please clarify what is to be done to the existing tc 12.30 design 6 sign support and sign mounted on it. There is no pay item for a new structure or sign but the note and summary on page 103 call for both being replaced. Thanks

Question Submitted: 2/29/2008

Question Number: 2

On sheet 44 Ashley Wood intersection P-2 and P-3 are under ref. # 63 Curb, Type 6, as per plan. 1.How much concrete fill is required at this locations? 2.Is the Curb and Gutter, Type 2 a 9" or 12" gutter plate? 3.Does the expansion detail on sheet 91 apply to the Curb and Gutter?

A: The amount of concrete fill required will be dictated by the contractor's construction methods to allow construction of the Type 6 curb, As Per Plan along Ashley Drive.A: The curb and gutter shall be constructed as per Standard Drawing BP-5.1 (07-28-00) as shown on the Title Sheet.A: The curb and gutter shall be constructed as per Standard Drawing BP-5.1 (07-28-00) as shown on the Title Sheet.

Question Submitted: 2/29/2008

Question Number: 3

1)In addendum No 1, It notes that the contractor is required to run a 4" conduit and run the fiber underground to the require manhole as per attached drawing. Where can we find the drawing?2)Addendum no 1 also states that work cannot start until March 1, 2009, Is this correct?3)In addendum no 1, page 3 states that an ODOT approved sub must be hired to relocate the existing artimis fiber. Does this sub need to pocess the work type 56 as noted further back in the addendum under fiber optic installation?

Question Submitted: 2/29/2008

Question Number: 4

In Addendum #1 pages 3 & 4 (see below) under the the Artimis paragraph you reference attached drawings. Where are the attached drawings?ARTIMISThe contractor shall be required to hire an ODOT approved sub to relocate the existing ARTIMIS fiber from the ARTIMIS pole at the SW comer ofl-275 and SR 127 (between the exit ramp and mainline) to the existing manhole at the NW comer of Waycross Rd. and SR 127. "See drawing". The fiber is currently located on Duke Energy poles and will need to be relocated to the new poles that will be in place at the time this project is sold. From the last new pole in the run at Waycross Rd. the contractor will be required to install a 4" PVC Conduit and run the fiber underground to the required manhole as detailed in the "attached drawing".

Question Submitted: 3/12/2008

Question Number: 5

In reviewing the response to question no 2 concerning the curb & Gutter, type 2. The plans say nothing concerning the thickness of the gutter plate, therefore, per std drawing BP-5.1, the thickness is 9". Please review.

Question Submitted: 3/14/2008

Question Number: 6

In reviewing addendum number 3 and comparing to addendum number 2. It appears that CBT will be the utility that will be done last. The date given in addendum number 2 is September 30, 2008. Addendum Number 3 confirms that work cannot start until March 1, 2009 unless approval is granted by the engineer when an area is cleared. Why not a start date of October 1, 2008 when CBT is supposed to be cleared?

Question Submitted: 3/3/2008

Question Number: 7

On Plan Sheets 17, 19, and 23 there are several large areas denoted "Full Depth Pavement Replacement Limits". However, reviewing the bid quantities, there does not appear to be enough pavement removed quantity to account for these areas.How will this work be paid for?

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.