

Ohio Department of Transportation

Prebid Questions

Project No. 080203

Sale Date - 3/26/2008

Question Submitted: 2/21/2008

Question Number: 1

Ref.5 Pipe removed 24" and under.Are the saw cut and pavement replacement for this item included in Ref.20 and 21?Ref.15 15"Conduit, Type B.Ref.16 Catch Basin No.3.Ref.17 Catch Basin No.3A.Are the saw cut and pavement replacement for these items included in Ref.20 and 21?

For the conduit removed and conduit placed, Reference No.'s 20 and 21 will be used to saw cut the existing pavement and replace the pavement in these areas.

Question Submitted: 2/27/2008

Question Number: 2

Item 20 - Full Depth Pavement Removal and Rigid Replacement - 1. Are there various patches, joint repairs, or sizable stretches of pavement? 2. What is the estimated average size of the patches? 3. Are the areas of replacement located on the ramp areas?

1. Most of the repairs should be joint repairs and the areas will be directed as per the project engineer. 2. Most joint repairs are 6 feet by the width of the pavement and the size will be directed as per the project engineer. 3. It is possible that repairs may be needed on the ramps. This determination will be made by the project engineer.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.