Ohio Department of Transportation Prebid Questions

Project No. 070528 Sale Date - 12/12/2007

Question Submitted: 11/28/2007

Question Number: 1

Ref. 45 638E02800 12" Water Main Polyvinyl Chloride Pipe and Fittings, ASTM SDR 26 is the bid item for the Water Work on this project. On plan sheet 6/36, the note states "All water mains shall be constructed of PVC, C-900 (DR-14)" The City of Heath uses C-900 (DR-14) pipe and not SDR 26 pipe. Will this item be corrected?

Question Submitted: 11/28/2007

Question Number: 2

On plan sheet 5/36 Construction Noiselt states that "do not operate power-operated constsruction-type devices between the hours of 7am and 7pm." Does that mean that the work is all to be done at night?

Question Submitted: 11/28/2007

Question Number: 3

Item 9 - Guardrail Type 5 Using 9' Posts listed in the proposal has a quantity of 50FT. Item 10 - Guardrail, Type 5 Long Span has a quantity of 222.00FT. In the Plans Sheet 12 of 36 shows the quantities for these two items reversed. Which of these are correct?

Question Submitted: 11/28/2007

Question Number: 4

Per the 2005 CMS manual the contractor may have the option to substitute a 3-Sided Precast Culvert placed on a cast in place slab bottom for a four sided box structure when shown on the plans. If a 3 sided precast arch culvert were to be provided in place of the box, would the use of pre approved precast concrete wingwalls be allowed as per the 2005 CMS instead of the Cellular Retaining Walls as per the plan notes?

The City of Heath wants to maintain the continuity of aesthetics along the bikeway with the other bike tunnel already constructed along this path. Therefore, Item 610 Cellular Retaining Wall (Concrete), As Per Plan will remain as stated in the plans.