

# Ohio Department of Transportation

## Prebid Questions

Project No. 100400

Sale Date - 6/3/2010

Question Submitted: 6/1/2010

Question Number: 1

The profile view on plan sheet 55 of 130 shows two runs of 8" sanitary sewer upstream of the proposed Manhole #3 at Sta 11+50.11. This 224' of 8" sanitary sewer and two manholes are not shown in the plan view nor was it included in the general summary. Please clarify whether or not this work is to be included in the bid. If it is to be included, please provide the appropriate bid items.

**The plan view on Sheet 55 is correct. The quantities and line items in the general summary on Sheet 23 are correct. The 224' of 8" sanitary sewer and the manholes at Sta. 9+84.66 and Sta. 11+44.66 in the profile view on Sheet 55 are to be disregarded. Please bid as is.**

Question Submitted: 6/1/2010

Question Number: 2

Why is the existing encased telephone cable not being relocated between 8+45 and 10+60? In this area there the 18' deep sanitary sewer sewer lies directly underneath the existing encased cable for approximately 80 lf. Furthermore, the proposed drop manhole at station 8+42 will undermine the existing telephone manhole and the 48" storm sewer if it is install at its plan location. Installing the sanitary sewer according as currently designed at this location is unsafe and will compromised the integrity of the adjacent underground facilities. Please consider relocating the underground telephone cable and manhole or realign the proposed sanitary sewer.

**Please bid the project as is.**

Question Submitted: 6/1/2010

Question Number: 3

Should PN-530 - Bituminous Price Adjustment be included in the project?

**Please bid the project as is.**

Question Submitted: 6/2/2010

Question Number: 4

Should the 36" Type B Conduit shown on sheet 56 be constructed as a sanitary sewer instead of storm sewer since this line is rerouting a combined sewer?

**The sanitary work on this project is only a portion of a future sewer separation project that the City of Newark is preparing. The sewer separation project will not be constructed until after this project is complete. Therefore, the installed sanitary lines as part of this project will not be operational. The 36" storm sewer being installed as part of this project will only discharge storm water upon the completion of both projects.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.