

Ohio Department of Transportation

Prebid Questions

Project No. 040326

Sale Date - 5/19/2004

Question Submitted: 5/17/2004

Question Number: 1

Ref. #53, 12" CIP Reinforced Concrete Piles, Driven, Plans indicate 60 ft. long piles to be furnished and driven. Existing power line, when relocated, approximately 4 ft. horizontally and 40 ft. vertically, will prohibit driving piles as we must maintain a 10 ft. horizontal and 10 ft. vertical clearance from all conductors. We therefore only have 30 ft. under the lines in which to work. This is not adequate for driving the 60 ft. piles.

This issue was addressed in the addendum #2. The addendum revised the abutment design with the piling to be placed at a skew, as detailed on revised plan sheets 21 & 22 included with the addendum. The District feels that the structure is constructible.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.