

Ohio Department of Transportation

Prebid Questions

Project No. 090454

Sale Date - 9/30/2009

Question Submitted: 9/10/2009

Question Number: 1

Plan Sheet 9 states that The State of Ohio will install, maintain and subsequently remove the detour signing. Sheet 9 also states that that contractor shall provide the local detour signing as per 614.06(B). Based on these notes, it would be the Contractor's responsibility to supply the detour signs and ODOT's responsibility to install and remove the detour signing. Is this assumption correct?

On Sheet 9/71, the State will be responsible for furnishing, installing, maintaining and removing the detour signage for the STATE detour (SR 303/83/82), as shown on the State Detour Map. The Contractor will be responsible for furnishing, installing, maintaining and removing the BOSTON ROAD detour (Grafton Road/Marks Road/Emmons Road), as shown on the Boston Road Local Detour Map. The Contractor is also responsible for furnishing, installing, maintaining and removing signs, gates, barricades and lights per MT-101-60. On Sheet 9/71, the State will be responsible for furnishing, installing, maintaining and removing the detour signage for the STATE detour (SR 303/83/82), as shown on the State Detour Map. The Contractor will be responsible for furnishing, installing, maintaining and removing the BOSTON ROAD detour (Grafton Road/Marks Road/Emmons Road), as shown on the Boston Road Local Detour Map. The Contractor is also responsible for furnishing, installing, maintaining and removing signs, gates, barricades and lights per MT-101-60.

Question Submitted: 9/22/2009

Question Number: 2

On sheet 7 of the plans a note states "A storm water permit shall be obtained from the OEPA by the contractor prior to beginning construction". Is this referring to the Co-permitte NOI form which is normally obtained by the contractor? Is a SWPPP required? Should there be a pay item?

Question Submitted: 9/25/2009

Question Number: 3

We tried to submit the bid via the internet and an error message states "30sep454.ebs" has 5 amendments applied but needs 4."Note that there are 5 amendments currently. Can you please check and update the EBS system as required?

Bid Express website is up to date now

Question Submitted: 9/8/2009

Question Number: 4

Could you please provide the "office calcs" used to generate the pavement quantities listed on page 10.

<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/MED-13363/>

Question Submitted: 9/9/2009

Question Number: 5

Could a link to the existing structure drawings for MED-252- 09640, 11652, 12296, and 12376 be made available?

The existing structure drawings are not available.

Question Submitted: 9/9/2009

Question Number: 6

The fourth paragraph on Plan Sheet 9 states that structure MED-252-11645 shall not be closed at the same time as structures 12296 and 12376. Structure 11645 is not referenced in any other location in the plans. Please clarify what Structure MED-252-11645 is referring to in an addendum.

Question Submitted: 9/9/2009

Question Number: 7

The fourth paragraph on Plan Sheet 9 states that structure MED-252-11645 shall not be closed at the same time as structures 12296 and 12376. Structure 11645 is not referenced in any other location in the plans. Please clarify what Structure MED-252-11645 is referring to in an addendum.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.

Ohio Department of Transportation

Prebid Questions

Project No. 080529

Sale Date - 9/10/2008

Question Submitted: 8/15/2008

Question Number: 1

I see that you have this listed as a culvert replacement, but I also see that you have three culverts and a box beam bridge on this bid. Do you have to have the Level 1 Bridge certification to bid this project?

Some of the work items require Level 1 Bridge work type. The prime contract must be qualified to perform at least 50% of the work items.

Question Submitted: 9/2/2008

Question Number: 2

Could you please provide the "Office Calcs" for the aggregate base and the bituminous asphalt items listed on page 10 of the general summary.

Question Submitted: 9/3/2008

Question Number: 3

Can the "office calcs" be provided for the pavement quantities?

Question Submitted: 9/5/2008

Question Number: 4

An existing single phase conductor crossing the centerline of SR 252 at Sta. 12+332.5 is to remain in place. It will interfere with the driving of the battered pile. What do you propose? Page 34/71 states a 508mm waterline is to be relocated by others. The proposal states it will be left in place. Which is correct?

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.