

Ohio Department of Transportation

Prebid Questions

Project No. 080645

Sale Date - 12/10/2008

Question Submitted: 3/19/2009

Question Number: 1

I had a question from a supplier about the reinforcing for the CIP piles. The reinforcing isn't included for the piles. Should there be any?

Question Submitted: 3/19/2009

Question Number: 2

It appears that the 16" Dia. Cast-In-Place Reinforced Concrete Piles shall contain rebar in accordance with SCD CPP-2-94 referenced in the Title Sheet. A portion of these piles will extend above the ground surface and are subject to potential buckling. The same Standard Drawing also requires the reinforcing to be included in the Reinforcing Bar List which it is not. Please clarify.

Please see addendum #1.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.