

# Ohio Department of Transportation

## Prebid Questions

Project No. 080077

Sale Date - 1/25/2008

Question Submitted: 1/21/2008

Question Number: 1

Plan sheet 12/77 of Part One indicates that "A changeable message sign" shall be on site for the duration of the project. Plan sheet 14/77 Short-Duration Closure of Multi-Lane Divided Highway shows 2 ea PCMS's to be used on the freeway. Back to sheet 12

**The quantity for Portable Changeable Message Sign, as per plan is for estimating purposes only. The actual duration and placement of the signs will be as directed by the engineer. The signs for the "Short Duration Lane Closure" shall be considered incide**

Question Submitted: 1/21/2008

Question Number: 2

This project is set up as four parts. In each part on the approach slab details sheet there is a note indicating that the rebar for the parapets is to be included with the parapet reference items. If you look at the reinforcing steel list sht. 75/77, it

**The parapet rebar is being paid for under Item 509, Epoxy Coated Reinforcing Steel, As Per Plan. The parapet bars are quantified on the Re-steel lists with the "R" prefix and carried to the Estimated Quantities. The approach slab item includes the 1" PE**

Question Submitted: 1/21/2008

Question Number: 3

Can the existing bridge drawings be put online?

**<http://www.dot.state.oh.us/contract/ftp/attach/PIC-81190/>**

Question Submitted: 1/21/2008

Question Number: 4

Can SIP forms be used on this project?

**No.**

Question Submitted: 1/21/2008

Question Number: 5

Item 203 Embankment, APP refers to As Per Plan Notes on the Structure General Notes. The embankment, As Per Plan Notes on sheets 57 (Part 1), 39 (Part 2), 38 (Part 3) and 54 (Part 4) state that embankment material is to be placed and compacted in 6ö lift

**The intent of the plan is for the embankment to be in 6 inch lifts within the limits of the cavity caused by the existing abutment removal. Granular Material, Type B, per Item 503, should be used behind the abutments. No addendum is needed.**

Question Submitted: 1/22/2008

Question Number: 6

It appears that benching will be required to construct the embankment for this project. There is no quantity set up for benching in the excavation and embankment items, nor is any benching shown on the cross sections. Please clarify if benching will be re

**Even though benching is not shown on the plans, the requirements of Item 203 must be met.**

---

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.