

Ohio Department of Transportation

Prebid Questions

Project No. 060318

Sale Date - 7/12/2006

Question Submitted: 7/5/2006

Question Number: 1

Page 12 of the plans. The last line of quantities for Pavement Planing (1039 S.Y.), Tack Coat (78 Gallon), and 448 Asphalt Concrete (50 C.Y.) for structures are included in the totals for Ref # 20, 21, and 22 in the proposal. These quantities are also accounted for under Ref # 47, 48, 49, 59, 60, 61, 64, 65, and 66 in the proposal. These items need to be reviewed and revised.

Page 48 of the plans. Structure PIC-22-19.30 has the following work description: Mill & fill this structure with an 1.5" asphalt concrete. Remove and replace the existing Polymer Modified Expansion Joints.

The existing expansion joint system has a concrete and steel end dam exposed and asphalt concrete meeting flush with the edges of the concrete end dam. There is no existing Polymer Modified Expansion Joints on this structure.

There is also a quantity of 1.35 C.Y. of Polymer Modified Expansion Joint set up. If there is no change in pavement elevation there will be no need for the Polymer Modified Expansion Joint.

Please review the work to be done on this structure as it does not match existing conditions.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.