

Ohio Department of Transportation

Prebid Questions

Project No. 090214

Sale Date - 4/1/2009

Question Submitted: 11/26/2008

Question Number: 1

Plan sheet 9 seems to indicate the existing concrete floor can remain in place. Is this interpretation correct?

The existing structure is to be removed as per ITEM 201E11000 STRUCTURE REMOVED as per the CMS (pay item shown on sheet 13/20). The limits of the removal of the existing structure will be as per the limits spelled out in the CMS. The bottom of the proposed box culvert will be located below the "floor" of the existing structure.

Question Submitted: 11/26/2008

Question Number: 2

We are to remove 480' of guardrail item 202E38000. But do we replace it and under what item??

The guardrail is being removed. There is no new guardrail being installed on this project. This project is utilizing Clear Zone Grading and by using this we have eliminated the need for guardrail.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.