

Ohio Department of Transportation

Prebid Questions

Project No. 090265

Sale Date - 4/29/2009

Question Submitted: 4/27/2009

Question Number: 1

Ref# 27 There is no detail for how wide this joint is. Normally this would be a Polymer Modified Asphalt Joint or just a 1" x 1" joint Sawed and Sealed.

The Bidders are reminded of the requirements of CMS 102.05 for a Site Visit at which the Bidders can measure the joint. According the 1990 existing plans the joint is approx 3"± x 3"± maximum but this approximation does not relieve the contractor from the EXISTING STRUCTURE VERIFICATION Note shown on sheet 8/14. The District chose to use the joint shown in the plan instead of others that are available. This joint was installed in the 1990 plan and has performed well for almost 19 years, there is no reason to change it.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.