

# Ohio Department of Transportation

## Prebid Questions

Project No. 060513

Sale Date - 12/13/2006

Question Submitted: 11/29/2006

Question Number: 1

After performing a field survey of the project, it appears that the existing asphalt thickness is significantly less than what the plans call out. It looks as if there is approx. +/- 2" of existing asphalt on concrete base. This will effect the milling of the 8ft shoulder. There will be a .25" difference between the top of the 19mm pavement and the top of the existing shoulder. Will that .25" need to be removed prior to placement of surface course. This also will raise the profile of the pavement by approx. 1.25", which will significantly increase the quantity of compacted aggregate required.

Question Submitted: 11/7/2006

Question Number: 2

Bid item 46 646 Center line 1.23 miles.

This quantity does not match plan sheet quantities. On plan sheet 34 it shows the Center line quantity to be 0.63 miles.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.