

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
4	01/07/2019	103908		TRU SR 46/82/East Market Street	Study of TRU SR 46/SR 82/East Market Street area.	Consultant to provide engineering services from PE (Stage 1 & 2) through FE (Final Tracings) including clearing the Environmental and On-Going services during construction. RW Acquisition Services are not included in this agreement.		
4	01/07/2019	105859	1200000.00	ATB SR 0046 19.99	Replace deck on SFN 0402915 ATB-46-19.99 over Mill Creek.	Consultant to provide engineering services from PE (Stage 1 & 2) through FE (Final Tracings) including On-Going Services during Construction. RW Acq services are not included in this agreement.	01/01/24	01/01/24
4	01/07/2019	106621		D04/D11 GES Tsk Ord FY19/20	Two year General Services task order agreement in Districts 4 & 11.	Consultant to provide General Engineering Services in Districts 4 & 11 as part of a 24 month Task Order. Estimated fee is \$1,500,000.		
4	01/07/2019	106885	1600000.00	SUM IR 0271 01.51	SFN 7708823 SUM-271-1.51 bridge deck replacement.	Consultant to provide engineering services from PE (Stage 1 & 2) through FE (Final Tracings) including On-Going Services during Construction. Geotechnical Services and	07/01/23	07/01/23

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
						RW Acq services are not included in this agreement.		
6	01/07/2019	105322	68500000.00	FRA IR 70 14.54 (Proj 2E)	Reconstruct and widen portions of IR 70 EB & WB between 4th St and Miller St to include ramps from Fulton Ave to IR 70 EB and IR 70EB to Parsons Ave. Reconstruct Mooberry St from Parsons Ave to 18th St and Fulton St between Third St and Fourth St. Reconstruct structures FRA-70-14.61, FRA-70-14.79 R, and FRA 70-14.93L&R. Construct eight retaining walls.	Provide construction inspection services and schedule review for project duration	03/28/19	04/08/19
<u>7</u>	<u>01/07/2019</u>	<u>108500</u>		<u>D07 CE FY19/FY20/FY21</u>	<u>District 7 general construction inspection services.</u>	<u>Construction Inspection Task Order to perform construction inspection services on various projects within the district. Duration of 24 months,</u>		

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	ProjectDescription	Consultant WorkDescription	Sale Date	Award Date
						<u>total contract amount</u> <u>\$2,000,000</u>		
8	01/07/2019	77942	2059000.00	GRE SR 72 18.76/18.83	For Bridge Nos. GRE-72 1876 and 1883, SFNs: 2902079 and 2902109 respectively: replace the existing concrete slabs on existing substructure units and perform other minor rehabilitation. The bridges carry SR 72 over the Little Miami River (1876) and a tail race to the Little Miami River (1883).	Consultant to prepare detailed construction plans through final engineering phase and prepare environmental document.	10/01/25	10/01/25
8	01/07/2019	84602	691000.00	BUT SR 122D 1.47	Replace bridge BUT-122D-0148, a 5 cell CMP pipe arch structure (87"x63") that carries SR 122 over the hydraulic canal in Middletown.	Preparation of detailed construction plans and environmental document.	01/01/25	01/01/25
8	01/07/2019	96666		D08 Bridge Underwater Insp FY20	Project to inspect various bridges	Inspection of various bridges over larger		

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
					over larger waterways that have piers in the water and require underwater dive inspections.	waterways that have piers in the water and require underwater dive inspections.		
8	01/07/2019	103849	6200000.00	WAR 22/48 3.03/8.63	Major Bridge repair WAR-221. Remove 1 1/4" of the existing wearing surface and overlay MSC.2. Remove and replace the existing strip seals with a glued in compression seal or foam expansion joints. The existing steel can remain but should be blasted clean and metallized.3. Blast clean and seal boxbeam ends under the expansion joints with a Silane Sealer. 4. Repair the deteriorated portions of the	Consultant to prepare detailed construction plans and environmental document for the major bridge repair.	01/01/20	01/01/20

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
					concrete with 519 patching. 5. Clean the scuppers. Include contingency quantities for any scuppers that cannot be cleaned. WAR-481. Replace the parapets with new parapets. 2. Clean the scuppers. 3. Replace the wearing surface with a new rigid overlay. 4. Patch the unsound portions of the substructure. 5. Replace the abutment bearings with elastomeric bearings. 6. Paint the structural steel with OZEU. 7. Seal the new barriers with Epoxy Urethane Sealer.			
9	01/07/2019	106381		D09 Underwater Brdg Insp 2019/20	Underwater inspection of	Underwater inspection.		

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
					various bridges in District 9 for FY2019 & FY2020			
11	01/07/2019	94211	1921734.40	BEL SR 7 9.79	Replace/line existing concrete pipe at SLM 18.30 and line existng CMP at SLM 14.49 along SR 7. Replace culvert at SLM 9.79.	Consultant to perform Preliminary and Detailed Engineering for replacement/rehabilitation of three structures, BEL-7-9.49, BEL-7-1449 (SFN 0700320) carrying SR 7 over Pinch Run and BEL-7-1830 (SFN 0700487) carrying SR 7 over Whiskey Run.	04/01/22	04/01/22
11	01/07/2019	107668	1100000.00	BEL SR 7 11.870	Provide new concrete overlay on deck and approach slabs. Perform partial depth deck repairs. Reset bearings.	Place MSC overlay on existing bridge deck. Perform deck condition survey to determine amount of partial depth repairs. Detail MOT phasing.	01/01/22	01/01/22
12	01/07/2019	11230	7000000.00	CUY SR 175 00.56	Replace the NS RR (Cleveland Commercial Railway) spur track bridge over Richmond Rd (SR-175) with a new overhead structure. This structure is located just south of Cannon	Two part scope, part 1., Conduct a structure type study and prepare AER. Increase SR 175 from 1 lane to 2 lane route. Part 2., prepare construction contract plans based on alternative chosen in study.	01/01/22	01/01/22

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
					Rd in Solon. The new structure span will provide clearance for a standard 2-lane roadway.			
12	01/07/2019	104101	200000.00	GEA SR 528 15.26	Replace the structure on SR-528 over a stream located south of SR-86 in Montville Twp	Prepare construction contract plans to replace the SR-528 bridge south of SR-86 in Montville Twp.	01/01/22	01/01/22
12	01/07/2019	107434		D12/D3 GES FY2020-2021 SUE	D12 and D3 Subsurface Utility Engineering Task order contract for SFY 2020-2021. This project is programmed to replace PID 102290 upon completion.	D12 and D3 Subsurface Utility Engineering Task order contract for SFY 2020-2021		
12	01/07/2019	107798	1666500.00	CUY IR 480 01.10 Noise Barrier	Construct Type II noise barrier project along IR-480 between Mackenzie Road and Fitch Road in the City of North Olmsted.	Prepare plans for a noise barrier installation in North Olmsted along I-480	01/01/22	01/01/22
12	01/07/2019	108459	1050000.00	GEA CU FY2021	Replace 12 deficient culverts	Prepare construction contract plans to replace 12 culverts in Geauga	04/01/21	04/01/21

Future Programmatic Date 01/07/2019

Sorted By District (Subject to Departmental Changes) Run Date 5/25/2018

Dist	Prgmtc Date	PID	Construction Cost	Project Name (ie CRS)	Project Description	Consultant Work Description	Sale Date	Award Date
					in Geauga County.	County. Work includes verifying culvert sizing and potential right-of-way needs.		