

Ohio Department of Transportation - Prebid Questions

Project No. 130185

Sale Date - 3/28/2013

ADA-83014 - SR-125-0.40

Question Submitted: 3/26/2013 9:55:41 AM

Is the Wearing Course included in the excavation quantities line item 7 or should there be a separate bid item?

Yes, Item 203, Excavation (Line item 7) includes the existing wearing course as per 203.01 of the CMS.

Question Submitted: 3/22/2013 9:06:11 AM

There are various locations on the project where existing guardrail retaining walls are to be removed. Is that work meant to be paid as part of the Clearing item or should there be a separate pay item?

No, the work should be paid for under Item 202, guardrail removed as referenced on sheet 11.

Question Submitted: 3/22/2013 9:02:22 AM

Sheet 31/52 shows "Granular Backfill" being placed behind the porous backfill to replace unclassified excavation area behind the new retaining wall. Is that meant to be paid as part of unclassified excavation item for that wall or should there be a separate item? Could you specify the type of granular material to be used?

The granular backfill shall be paid for with Item 610, Special, Retaining Wall, Misc.: Precast Reinforced Concrete Lagging Panel as specified in 610.09 of the CMS. The Granular Backfill type shall conform to 610.06 of the CMS.