

Ohio Department of Transportation - Prebid Questions

Project No. 140004

Sale Date - 1/9/2014

ADA-84432 - SR-125-19.68

Question Submitted: 12/23/2013 3:58:15 PM

The bearing stiffeners shown on page 13/32 show the stiffener to be field welded rather than welded by the beam fabricator. Will all the stiffeners in fact need welded in the field or was this a mistake in the plans?

The district prefers to have the stiffeners welded in the field to ensure they are centered on the bearing. Bid the plan as is.