

# Ohio Department of Transportation - Prebid Questions

Project No. 153047

Sale Date - 11/19/2015

ADA-87298 - US 52-12.49 Brdg Replace

*Question Submitted:* 11/12/2015 5:16:01 PM

Section 9.1 of the scope states that the Department has obtained a Regional General Permit for this project and it is located in the proposal. Where can this be found?

**The waterway permit will be added by addendum.**

*Question Submitted:* 11/12/2015 3:29:57 PM

Section 9.4 of the scope of services states that the consultant shall perform a detailed flood plain analysis for each waterway crossing. If the proposed bridge doesn't decrease the waterway opening at the bridge will we need to run a detailed flood plain analysis.

**Please see Addendum No. 2.**

*Question Submitted:* 11/12/2015 12:59:20 PM

Our field measurement of the bridge gave a height of 25'+/- from the deck to the stream. Since over the side drainage is prohibit at 25' and above will over the side drainage be allowed on this project?

**The railing used for the proposed structure will be dependent upon the structure type selected by the DBT. All requirements of the BDM shall apply.**

*Question Submitted:* 11/4/2015 9:56:19 AM

Section 12.2 requires a 10' lane.

Is this dimension f/f of barrier or is a 1' barrier offset required on both sides resulting in a 12 f/f of barrier dimension?

Please clarify as this affects part width construction cost.

**The 10 foot lane requires 1 foot minimum barrier offsets resulting in a 12 foot f/f of barrier dimension as a minimum.**

*Question Submitted:* 10/30/2015 2:35:33 PM

How much of the existing abutments must be removed?

**The only requirement for removal of the existing abutments is that no portion of the existing structure can be utilized in the proposed structure. The exact removal limits of the existing abutments will be determined by the DBT based upon this requirement. This information will be added to the scope by an upcoming addendum.**

*Question Submitted:* 10/8/2015 9:07:11 AM

Scope item 13.4 Roadway states "A minimum of 12'-0" lanes and 6'-0" paved shoulders shall be provided within the project limits". What defines the project limits for this pavement work?

**Please see section 5 of the Scope of Services.**

*Question Submitted:* 9/23/2015 9:30:36 AM

Can the electronic CAD files shown in the 87298-Attachments be provided by the Department for this project?

**[ftp://ftp.dot.state.oh.us/pub/districts/d09/P%26E/McClellan/ADA-52-1249%20\(PID%2087298\)/](ftp://ftp.dot.state.oh.us/pub/districts/d09/P%26E/McClellan/ADA-52-1249%20(PID%2087298)/)**