

Ohio Department of Transportation Prebid Questions

Project No. 091037

Sale Date - 6/10/2009

Question Submitted: 6/8/2009

Question Number: 1

ref 46 pile reinforcement show the verticals hooked, but the rebar list calls it out as straight, are hooks reqd. and if so, are they standard length and is that length included in the 27'-0" given?

The pile reinforcement should be a 90 degree bend. The bend is the standard length. It is not included in the 27'-0".

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.