

Ohio Department of Transportation - Prebid Questions

Project No. 140554

Sale Date - 11/26/2014

ASD-93864 - Mohican SP Campground

Question Submitted: 11/21/2014 5:00:54 PM

With the change in pavement repair quantity in addendum #3 the contractor will not be able to supply the department with the amount of asphalt grindings app as required per the contract documents. please review this item.

The intent of this pay item was for the contractor to deliver any/all asphalt grindings generated by the project up to a maximum of 1000 cy to a location specified by ODNR. The amount of asphalt grindings generated by the project will vary from plan quantity due to normal differences between actual and field measurements. If the 1000 cy runs under, the contractor will be paid for this difference per the requirements of C&MS 104.02.

Question Submitted: 11/14/2014 2:58:32 PM

On Page 7, Picnic Area – 442 Asphalt Surface 9.5 MM, Type A has a quantity of 678 CY. The total area is approximately 4400 SY. Quantity appears to be incorrect, please check and revise quantity if needed. On Page 8, Main Road – 253 Pavement Repair, Misc.: Partial Depth (max. 4”) has a quantity of 1809 CY. The total area of the Main Road is approximately 9300 SY. Quantity appears to be incorrect, please check and revise quantity if needed.

An addendum has been posted addressing these questions. Clouded and clean plans sheets have also been developed for these changes.

Question Submitted: 11/13/2014 2:50:18 PM

On Page 2 typical sections the Roadway Typical shows 1.5' of berm and the Campsite & Parking Lot Typical show 6" berm. Do the Campsite and Picnic Area Roadways get 1.5' of 617 Berm? Do the 10' x 50' trailers pads get 6" of 617 berm around them?

All roadways throughout the campground are to receive a 2' wide 617 berm. All campsite trailer pads and parking lots without curb are to receive a 6" wide 617 berm.

Question Submitted: 11/13/2014 11:12:27 AM

Per the notes on page 3 of the plans it states: That two way traffic shall be maintained at all times except for various culvert replacement locations. Work hours are Mon. – Thurs. 6:30am to 9:30pm and Friday 6:30am to 1pm. Will the entire areas of work be open and free of campers and trailers to the contractors during these hours?

Yes. There are no permanent campers at the state park. The project intent is to construct this project prior to the campground opening for business in calendar year 2015.

Question Submitted: 11/6/2014 4:48:07 PM

With 4 days before bid and the addendum adding and changing a good portion of the project which will require the a re-revisit the job to check out work and flow lines for drainage work not shown on plans, is ODOT going to change the bid date?

Sale delayed to 11/26/14.