

Ohio Department of Transportation Prebid Questions

Project No. 070184

Sale Date - 4/18/2007

Question Submitted: 3/20/2007

Question Number: 1

1. The existing shoulder is constructed of what type of material? (Concrete, asphalt)2. The proposed edgedrain ditch is to be how deep? The standard drawing (DM-1.2) shows 18" + 5" = 23" deep. The typical section shows 18" + the thickness of existing concrete pavement (which we do not know) or do you want something else?3. Is the 301 bituminous aggregate base plug, as shown on the standard drawing, required?

Question Submitted: 4/4/2007

Question Number: 2

THERE IS NOT A DESIGN REQUIREMENT FOR PLANT MIX PAVEMENTS LISTED IN THE PROPOSAL-WAS THIS INADVERTENTLY LEFT OUT ?

The project uses Item 442 which is designed by actual traffic counts from ODOT's website listed in the General notes sht. 3/37 of the plan. No items in the plan require design requirements specified in the proposal.

Question Submitted: 4/5/2007

Question Number: 3

It appears the existing shoulder consists of concrete overlaid with asphalt. With respect to the 18" prefabricated edge underdrains, must they be installed as plans show at edge of pavement or can they be relocated to edge of shoulder to eliminate the need of trenching through concrete shoulder?

Question Submitted: 4/6/2007

Question Number: 4

Plan sheet 1 of 37 lists Supplemental Specification 800 dated 3-14-07. I can not seem to locate this specification. Please advise.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.