

# Ohio Department of Transportation - Prebid Questions

Project No. 130186

Sale Date - 3/28/2013

ATB-78399 - LR-WEST AVENUE-1.81

*Question Submitted:* 3/25/2013 5:48:46 PM

On plan sheet 13 it is shown that the portable concrete barrier on bridge 1.89 is to be anchored. Please provide the number of anchors required per barrier and provide a bridge mounted barrier bid item. On structure 1.81 at the bridge ends where a portion of deck gets removed plus backwalls should the barrier be anchored in these areas?

**The number of anchors has been given on sheet 13. Bridge mounted PCB has been added. Structure 1.81 will not have anchored PCB.**

*Question Submitted:* 3/25/2013 5:45:37 PM

The completion date per proposal is October 15, 2013. Under the Maintenance of Traffic notes on plan sheet 7 of 52 it states that November 14 shall be considered an interim completion date. Why is there an interim completion date after the project completion date? Is the project completion date correct taking into consideration that both bridges have field painting of the existing structural steel required?

**The Winter Limitation Note has been deleted.**

*Question Submitted:* 3/14/2013 3:19:36 PM

Ref# 70 includes the rebar for the approach slabs, but the notes indicate that the rebar for the approach slabs should be included with the approach slab reference. Please clarify.

**The rebar quantity for the approach slabs has been removed from the bid reference.**