

Ohio Department of Transportation - Prebid Questions

Project No. 130476

Sale Date - 8/1/2013

ATB-78883 - SR-531-2.90, PART 1;ATB-531-2.40, PART 2

Question Submitted: 7/30/2013 3:52:50 PM

Addendum 1, Special Provisions 14 lists 1600 C.Y. of sand prefill. Where is this item paid?

The 1600 C.Y. of Sand Prefill is to be included in Bid Reference #26.

Question Submitted: 7/27/2013 8:50:03 AM

The quantity for line item 157 Concrete Steps appears to be wrong. Please review and advise.

Steps, including the landings, are paid by width of each step, as per RM-2.1: 47 steps x 4FT width = 188 FT

Question Submitted: 7/27/2013 8:46:08 AM

Part 1 and Part 2 Drive Summary sheets note 2 states that the asphalt driveway removals are to be paid under item 203 excavation. Please provide quantities for this work and add them to the excavation bid items.

The quantities for the "driveway" excavation work are included in the plans; please bid as shown.

Question Submitted: 7/27/2013 8:38:52 AM

Part 2 Cross Sections pages 42 to 44 have no listed quantities? Please provide quantities for these sections.

The layer displaying quantities on these sheets was inadvertently turned off, however the earthwork quantity for these sheets is included in the total shown in the bid proposal for references 148 & 150;

Bid as shown. Sheet 41: C = 10 CY, F = 0 CY; Sheet 42: C = 76 CY, F = 0 CY; Sheet 43: C = 199 CY, F = 0 CY; Sheet 44: C = 101 CY, F = 1 CY.

Question Submitted: 7/26/2013 9:03:07 AM

I noticed that ref #'s 88, 89, and 207 are specified 707.41. Typically underdrain is specified 707.31. Is this a mistake?

The requirement of 707.41 is not a mistake; please bid as shown.

Question Submitted: 7/25/2013 11:43:09 AM

The Proposal appears to be missing the Proposal Note for the Asphalt Binder Price Adjustment. Please add via addendum.

Proposal note 535 is only for use on all multi-year projects that specify asphalt concrete with a minimum of 2500 CY for any contract item listed in the Schedule of Contract Items;

No asphalt item on this project meets this threshold.

Question Submitted: 7/25/2013 11:03:57 AM

Please clarify the clearing and grubbing notes associated to the lakeward slopes. Plan note on sheet 6a states "All trees on the lakeward slopes are to be removed within the construction limits shown on the plans." Plan pages 26 - 42 state "Remove portion of woods needed to construct new embankment construction". Are all trees and brush to be cleared from the North edge of SR 531 to edge of water?

Yes, all trees on the lakeward slope are to be removed as per the Clearing and Grubbing general note.

Question Submitted: 7/25/2013 10:53:54 AM

Has an asbestos survey been performed on parcel 14-WD, 1 Story frame residential, slated to be demolished under line item 114. If so, could the department please provide a copy of their findings.

The Asbestos survey information has already been provided in the bid documents as special provision - asbestos demolition survey report, parcel 14, dated 1/26/12. Please see the Special Provisions section after Part 2 of the plans.

Question Submitted: 7/17/2013 11:13:54 AM

On sheets 36 and 37 of 139 the storm sewer pipes call out to be 15" Type C. Should the pipe running under the driveways be Type B?

L&D Volume 2, Section 1104.1: Type B conduit shall be specified for storm sewers under pavement, paved shoulders and commercial or industrial drives and Type C conduits for storm sewers beyond those limits. The storm sewer running parallel with the road is not under the pavement and therefore should be Type C.

Ohio Department of Transportation - Prebid Questions

Question Submitted:

7/11/2013 12:01:46 PM

Could you please provide a link to the Pavement office Calcs?

**Please see the following link to the FTP site for Project 130476 pavement calculations.
<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/ATB-78883/Reference%20Files/>**