

# Ohio Department of Transportation - Prebid Questions

Project No. 120282

Sale Date - 5/10/2012

AUG-85239 - VA-BH-FY201

*Question Submitted:* 5/9/2012 7:58:52 PM

Will Department clarify that PN 552 does not apply on this project?

**We are not applying PN 552 to this project.**

*Question Submitted:* 5/9/2012 7:46:37 AM

Can the department make the existing structure plans available online?

**<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/AUG-85239>**

*Question Submitted:* 5/8/2012 11:01:13 PM

Regarding the sealing of Epoxy-Urethane on the piers. Previous question asked if there would be bid items established for the removal of existing sealer before the new sealer is applied. Per the Departments response that existing sealer removal will not be required, does this apply to all sealing being done, not just the actual areas that are being patched?

**The previous response should have stated that no pay item will be established for removal of existing coatings. The contractor shall follow CMS 512.03.F. Surface Preparation.**

*Question Submitted:* 5/8/2012 11:16:43 AM

Please advise what the scope of Ref Item #0006 (Jacking & Temp Support on AUG-67-0345) is intended to be.

**The jacking and temporary support is necessary due to the repair work on column 7 on the rear pier as shown on sheet 12/44. The concrete on this column is completely shattered and the limits of the proposed chipping go completely around the pier which will weaken it more. The contractor will need to support the pier cap during this work.**

*Question Submitted:* 5/7/2012 9:43:58 AM

Half of the bridge locations have existing epoxy-urethane coatings on the pier columns. Can you add payitems for removal of existing coatings as these locations?

**It is not necessary to remove the existing epoxy-urethane coatings prior to patching and re-sealing.**