

# Ohio Department of Transportation Prebid Questions

Project No. 060521

Sale Date - 12/13/2006

---

Question Submitted: 11/20/2006

Question Number: 1

Part 1 Belmont County SR 7

Is it necessary to form a hot longitudinal joint between mainline and 8' shoulder?

**As per the CMS, a hot longitudinal joint between the pavement and the paved 8 foot shoulder will be required.**

Question Submitted: 12/5/2006

Question Number: 2

Part 1 SR 7 Item 209 linear grading

The general note for this item states that all debris, material, vegetation, etc., is to be removed from within the linear grading limits. The area shown on the page 10 of the plans from SLM 3.6 to SLM 4.79 is quite wide. Could you please define the limits of the linear grading as a certain width from edge of paving? Would this area fall under item 209 Ditch Cleanout?

**On the Shoulder Data sheets (10 and 11) it is called out in the columns labeled "Proposed Width" and the specific column is the "B" columns, both Left and Right. Dimension "B" is the width of the Item 209. Linear Grading.**

---

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.