

# Ohio Department of Transportation - Prebid Questions

Project No. 140098

Sale Date - 2/18/2014

BEL-86871 - IR 70 4.41/ 4.71

*Question Submitted:* 2/14/2014 10:03:12 AM

The plans do not have any pay items for the parapets. Where is this paid?

**The quantity of concrete for the parapet on the deck has been included in Item 511 E 21538 Class QC2 Concrete with QC/QA, Superstructure. Please see the Structure Quantity Calculations.**

**The cost of the parapet concrete on the approach slabs has been included in Item 526 E 25000 – Reinforced Concrete Approach Slabs (T=15”). Please see note 3 on plan sheets 124/164 and 152/164.**

**Bid the project as is.**

*Question Submitted:* 2/12/2014 11:12:15 AM

With new work being performed on the piers and abutments, should there be a reference item to add crushed aggregate slope protection under the bridges?

**No work will be required on the existing crushed aggregate slope protection.**

*Question Submitted:* 1/31/2014 2:30:01 PM

Can the existing bridge plans be posted on ODOT's ftp site for review?

**The existing plans have already been posted to <ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/BEL-86871/>**