

Ohio Department of Transportation - Prebid Questions

Project No. 100506

CLA-25329 - SR-4-23.12

Sale Date - 10/7/2010

Question Submitted: 9/29/2010 8:42:52 AM

The plans reference Temporary Sheeting and Temporary Fills. However, there isn't a bid item for Cofferdams, Cribbing & Sheeting. Will there be a bid item added?

We will add item 503 Cofferdams and Excavation Bracing, As Per Plan by addendum.

Question Submitted: 9/27/2010 9:47:18 AM

The link provided for the existing plans (<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/CLA-25329/>) leads to an empty folder.

Question Submitted: 9/23/2010 11:43:43 AM

On the Bridge plan sheets 19, 20, & 21, 3' wide Neoprene sheeting is shown, but no pay quantity is shown in the estimated quantities or the proposal items.

See forth coming addendum.

Question Submitted: 9/22/2010 6:55:42 AM

Can plans for the existing structure be posted on the ftp site?

<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/CLA-25329/>

Question Submitted: 9/21/2010 9:05:49 AM

Are anchors required for 622 Portable Concrete Barrier, 32" Bridge Mounted? If so, how many anchors are required for each section?

Anchor bolts are not required.