

Ohio Department of Transportation - Prebid Questions

Project No. 140069

Sale Date - 2/6/2014

COL-86994 - SR-154-14.04

Question Submitted: 2/3/2014 8:27:39 AM

On Sheet 25 of the plans, it shows Item 203 Granular Material Type B to be used in between the existing and proposed rear abutments. How is this Item to be paid? Is it to be included in Item 203 embankment or should this be a separate pay Item?

The Embankment with Granular material is to be included in Item 203 Embankment for payment.

Question Submitted: 1/30/2014 8:32:09 AM

Please clarify the quantity of the 1/2*6*10" bent plates shown on 28/52 and 29/52.

This is part of a Lump Sum item for Item 503 Cofferdams and Excavation Bracing, As Per Plan. The quantities needed are to be determined by the Contractor.

Question Submitted: 1/28/2014 10:14:43 AM

Based on NPDES permitting, should a site plan and storm water pollution prevention plan be added to the general summary page? There is over 1 acre of EDA for this bridge site.

A site plan will be provided and a quantity for Item 832 Storm Water Pollution Prevention Plan will be added by addendum.