

Ohio Department of Transportation - Prebid Questions

Project No. 116089

Sale Date - 11/10/2011

COL-91520 - SR-7-(17.80)(19.20)

Question Submitted: 11/7/2011 12:11:20 PM

This is for 116089 Col SR 7-17.80)(19.20)

Plan sheet 12/16 gives a plan view of the work at 19.20 to be completed in both lanes. The culvert extension is indicated to be completed at the outlet end and the northwest corner of the structure. This is clearly visible from the field. The plan shows the concrete lagging wall to be completed on the southeast corner of the project. A field visit indicates that the embankment in this area is completely flat, there is no slope failure in this area and all of the soil bore holes are on the northwest side. Can this be verified by ODOT that the plans have identified the work to be completed in the wrong area. This change will greatly alter the construction sequence and the contract bid quantities.

The plans were prepared in accordance with the approved DSR for this site. The slope issues along the culvert outlet will be resolved with the culvert extension.

Question Submitted: 11/7/2011 8:37:49 AM

Project: 116089. Cover depth is not shown over COL-7-19.20 DSR COL-006. Long-span guardrail is shown on one side but not on the other. Is the intent to attach guardrail to existing structure per GR-2.2? If so please add Standard Construction Drawing GR-2.2 to plans. If not please clarify.

The existing guardrail on the right side is standard guardrail. Due to the emergency nature of the project, additional data on the depth of cover is not available. There is no intent on attaching the proposed guardrail to the existing box.

Question Submitted: 11/1/2011 2:34:00 PM

Are any core borings for this project?

Yes, there is soils information that will be provided at the Pre-Construction meeting.

Bid the project as is.