

Ohio Department of Transportation

Prebid Questions

Project No. 070116

Sale Date - 3/7/2007

Question Submitted: 2/19/2007

Question Number: 1

Please verify the total of the concrete barrier, single-slope type B, A.P.P. On sheet 16, per median pier protection detail GR-27, it shows 78'4" out-out of the pier columns with 19' @ each end of the outside pier. Should the total be 116'4" (19'+78'4"+19')?

Question Submitted: 2/19/2007

Question Number: 2

For Item concrete barrier, end section type B, on sheet 19, note 14 refers you to the standard RM 4.6, which has a concrete base w/reinforcing steel. The note 14 then continues.. base of this end section to be same as detailed in section A-A, which the wall sets on the asphalt concrete base. Please verify which way this is to be constructed.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.