

Ohio Department of Transportation

Prebid Questions

Project No. 090109

Sale Date - 2/25/2009

Question Submitted: 1/28/2009

Question Number: 1

There currently is no bid item for Cofferdams, Cribbs, and Sheeting. How is the contractor to be paid for work that is usually paid for under this item.

This pay item is not needed since the MOT is a detour. The only excavation is behind the abutment, and that could be laid back at 2:1 during construction.

Question Submitted: 1/28/2009

Question Number: 2

Please make existing structure drawings available for DEL-257-1430 over Bokes Creek. Thanks.

Question Submitted: 1/28/2009

Question Number: 3

Please make existing structure drawings available for DEL-257-1430 over Bokes Creek. Thanks.

<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/DEL-77562/>

Question Submitted: 1/28/2009

Question Number: 4

Can hoe-rams be used to remove the 17-inch thick superstructure?

Since we want to preserve piers and portions of abutments, Hoe-Rams are not permitted for removal of the slab. Structure Notes on sheet 23/38 provide guidance on removal requirements.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.