

Ohio Department of Transportation

Prebid Questions

Project No. 091009

Sale Date - 5/20/2009

Question Submitted: 5/14/2009

Question Number: 1

The sequence of operations on sheet 6 of the plans for phases 2 and 3 we are to plane the pavement 1.75" . Note 4 then states immediately place the intermediate course. Is it the intent that the intermediate course be placed the same day? A permanent closure with barrels is allowed so that the 1.75" drop-off should not be an issue.

As stated in the note on sheet 5 labeled "Work Restrictions And Lane Closures", areas that are planed shall not be opened to traffic. The same note tells the contractor that he/she shall maintain at least one lane of traffic at all times. Therefore, the contractor could plane one lane of traffic in each direction while maintaining traffic in the adjacent lane (utilizing barrels according to standard drawing MT-101.90). The contractor would be required to place the asphalt concrete intermediate course on the planed surface before he/she could open traffic to these lanes. The plans to not specify any lane closure restrictions for Interstate 77 throughout the limits of this project.

Question Submitted: 5/8/2009

Question Number: 2

Reference 6, Item 442 Asphalt Concrete Surface Course, 12.5mm, Plan quantity is 5758cy. Quantity in the Proposal is 7072cy. Is there a correction to the quantities for this Item ?

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.