

Ohio Department of Transportation - Prebid Questions

Project No. 108056

Sale Date - 9/16/2010

HAM-88234 - IR-DEMOLITION;IR74/75

Question Submitted: 9/14/2010 2:02:06 PM

Bid Item 33 & 19 - What is required at these vacant lots.

Bid Item 19 and 33 shall be demolished per Item 202 Building Demolished, As Per Plan note on sheet 2 of 12.

Question Submitted: 9/14/2010 1:57:43 PM

Bid item #44 Where do you include the asbestos inspection fees. Should that be a seperate bid item?

Per the Environmental Work (Asbestos Abatement) note on sheet 2 of 12 Asbestos Inspection is to be included in the Item Special - Asbestos Abatement Lump Sum.

Question Submitted: 9/14/2010 1:55:13 PM

Bid item # 43 - What type of material is the 600 cf in this bid item.

Bid item #43 was included in the plan to cover those items not covered under the other pay items. The item was set up for bulk items that may contain ACM material. An example of this type of material would be furnaces that may contain ACM gaskets.

Question Submitted: 9/14/2010 1:51:47 PM

Bid Item #44 - What is this LumpSum in the Unit referring to?

The Lump Sum unit for Bid Item #44 is referring Environmental Work (Asbestos Abatement) note on sheet 2 of 12.

Question Submitted: 9/10/2010 4:18:01 AM

There is no indication of the type or size of the Overhead Sign Supports that are included in Ref No. 4

Item No. 630E89702 REMOVAL OF OVERHEAD SIGN SUPPORT & DISPOSAL does not specify the type or size. These are not standard odot signs. This item includes the removal of the signs located on parcel 226 and 840. CMS 102.05 states that Bidders must, "Carefully examine the Bid Documents and perform a reasonable site investigation before submitting a Bid."