

# Ohio Department of Transportation

## Prebid Questions

Project No. 080066

Sale Date - 1/25/2008

Question Submitted: 1/16/2008

Question Number: 1

This question is regarding Addendum No. 2. The Addendum indicated that the color of asher stone will be selected by the project engineer. □□ The question is regarding the application of the color. The color can be applied at the job site or at the precast y

**The color can be applied at the jobsite or the precast yard. The color does not have to be pigmented precast.**

Question Submitted: 1/16/2008

Question Number: 2

1) The Conduit items don't specify any certain type of pipe material, but in the cross sections you are specifying RCP pipe material for all conduit runs. What type of conduit should we be bidding? Please Clarify. □□□ 2) Sheet 21 of 49 at sta. 8+00 and sheet

Question Submitted: 1/16/2008

Question Number: 3

Can the Microstation CAD Files be made available online. Also Can you make the Existing and Proposed Surfaces available in LandXML Format.

**<http://www.dot.state.oh.us/contract/dgn.htm> □ Unfortunately, the existing and proposed LandXML files are not available for this project.**

Question Submitted: 1/16/2008

Question Number: 4

The EBS file for Addendum #1 eliminated Reference #52 Asphalt Concrete Surface Course, and added an additional Reference Item for Intermediate Course Asphalt. Therefore, the EBS file now has 2 line items for Intermediate Course and no Surface Course. Plea

Question Submitted: 1/17/2008

Question Number: 5

Is the note on plan sheet 35 regarding Vandal Protection Fence intended to require vinyl coating of the posts, braces and framework? Would a coat of black paint be sufficient as long as the color matches.

Question Submitted: 1/17/2008

Question Number: 6

Is a bid item for 108E10000 CPM Progress Schedule going to be added? If not, where are the costs for this work to be covered and paid?

Question Submitted: 1/17/2008

Question Number: 7

Completion date for this project is listed as 08/15/2009. Field Office, Type B quantity shown as 7 months. Please clarify.

Question Submitted: 1/17/2008

Question Number: 8

Bid item 19 Concrete Barrier Single Slope Type D. After deducting the 80 LF for the four Type D inlets shouldn't the quantity be only 8 LF? Also it seems the inlets need to be moved to allow room for the Type D End Sections.

Question Submitted: 1/17/2008

Question Number: 9

Will the weathering steel fascia beams have a shop prime? For Item 514 reference to BDM Section 302.4.1.5a, it indicates a three coat and there are no items for surface preparation or prime coat.

Question Submitted: 1/17/2008

Question Number: 10

The plan cross sections indicate that the existing roadway is to be removed and that the excavation quantity is accounting for that removal. Does the plan embankment quantity account for placing embankment in the area outside of the new embankment where t

Question Submitted: 1/17/2008

Question Number: 11

Bid Item #33 is Class C Concrete, Headwall with a quantity of 3 CY. Is it the intent to have the headwalls for this project cast in place or should this bid item be Concrete Masonry instead? Also, please supply details on the type of headwall required (H

---

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.

## Ohio Department of Transportation Prebid Questions

Question Submitted: 1/17/2008

Question Number: 12

On sheet 37 of 49, the first item in the Legend indicates that item #840 Wall Excavation is to include item 203 Embankment returned. Please supply the quantity of embankment to be returned for the area indicated in the legend.

Question Submitted: 1/17/2008

Question Number: 13

Line item # 0017 606E60024 Impact Attenuator, Type 2-98 (Bi)(speed 60mph), (Hazard width 360 inches), (WT:36) 2 ea. ☐ ☐ Is 360 inches the correct width? ☐ ☐ Would Trinity's Family of Crash Cushions fit the criteria for this line item? ☐ ☐

Question Submitted: 1/18/2008

Question Number: 14

Supplemental Specification 840 states in 840.06 Construction; Section "J" Pile Sleeves: place bentonite slurry in void between the pile and the sleeve. On recent projects they Value Engineered from bentonite to sand. Specifically natural or manufactured sand

Question Submitted: 1/18/2008

Question Number: 15

The project has bridge piling ( HP10x42 ) driven to bedrock. There is not a bid item for pile points, should the item be added ?

Question Submitted: 1/18/2008

Question Number: 16

Plan sheet 8/49 shows Portable Concrete Barrier on the outside shoulders protecting the MSE Wall and abutment construction. the plan sheet does not show any Portable Concrete Barrier on the median shoulders to protect the pier and median construction. Sho

---

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.