

# Ohio Department of Transportation

## Prebid Questions

Project No. 060491

Sale Date - 11/15/2006

Question Submitted: 10/18/2006

Question Number: 1

on sheet 13 of the plans, the pay quantity for center line is 4.64 miles. the proposal has the solid line equ. quantity of 6.07 miles. please clarify.

Question Submitted: 11/7/2006

Question Number: 2

ODOT 491(06) LIC USR 40

Item 202 Base Removed, APP & Item 613 Low Strength Mortar Backfill, both of these items refer to the concrete base transverse joint removal and replacement, Pg 5/20. Is the use of 613 Low Strength Motor the correct application for this material? It is generally used for conduit backfill and shouldn't be used within 3 feet of the subgrade. If the intent is to remove the entire concrete base to subgrade then a sawcutting item needs to be added. How are we to maintain traffic with a drop off of 8" in the adjacent lane if the setup time of repair material requires the lane to be closed overnight?

**Addressed in a previous addendum.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.