

# Ohio Department of Transportation

## Prebid Questions

Project No. 085001

Sale Date - 4/23/2008

Question Submitted: 4/15/2008

Question Number: 1

On drawing 5/9 in the contract drawings under proposed, note C state, "JACK THE EXISTING SUPERSTRUCTURE AT PIER 1 AND INSTALL ALL TEMPORARY SUPPORTS NECESSARY TO PERFORM THE WORK ACCORDING TO THE STRAIGHTENING PLAN." Is this note suggesting that the concrete deck only needs to be supported at Pier 1 when removing the existing damaged main members, or do we have to support the deck the full length of the beams being replaced?

**The note is not intended to suggest that the concrete deck only needs to be supported at pier 1. Additional temporary support(s) may or may not be needed depending on the contractor's work plan. The contractor-prepared straightening work plan is to provide details of all procedures and any temporary support(s). This plan will be prepared in accordance with SS 849 and submitted and approved by ODOT prior to beginning work.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.