

# Ohio Department of Transportation

## Prebid Questions

Project No. 060134

Sale Date - 3/8/2006

Question Submitted: 2/24/2006

Question Number: 1

ODOT Project 060134

Page 9/54 – Item 614, Maintaining Traffic – Phase I & II specifically state that lanes would be closed and portable barrier wall placed during bridge construction. This requires that one 12' lane of traffic is to be maintained at all times. Pages 14/54 & 14A/54 show double lane shifts and crossovers to maintain traffic. We are assuming, unless otherwise directed, that pages 14 & 14A are for reference only and were not intended to require the contractor to maintain traffic in this fashion

**In both Phase I and Phase II MOT on Sheet 9, the traffic lane is shifted 4.5 Feet onto the shoulder for the MOT and Transition Area Delineation is required for the shifting of the lane. Sheets 14 and 14A are standard plan insert sheet with the requirements for the Transition Area Delineation, only the Transition Area Delineation requirements for the edge lines is applicable on this project since only one lane is being maintained**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.