

# Ohio Department of Transportation

## Prebid Questions

Project No. 101026

Sale Date - 3/11/2010

Question Submitted: 1/26/2010

Question Number: 1

Please clarify the note on page 10 for item 253 Pavement Repair. Pavement SHALL be planed before pavement repairs are performed. IF pavement planning is performed prior to pavement repairs, the repairs shall be 6" thick. Please clarify the note on page 12 planed surfaces. If the plan intent is to mill then do pavement repairs. 5 days on a milled surface is a short widow of time.

**The pavement shall be planed before pavement repairs are preformed and the repair will be 6" thick. The days planed surface shall be open to the public has been increased to no more than 7 days.**

Question Submitted: 1/29/2010

Question Number: 2

Please clarify the intersection calculations on sheets 14&15; it appears that the quantities are wrong column.

**The intersection calculations were corrected on sheet 14. The totals were corrected on sheet 15 from the changes that were made on sheet 14.**

Question Submitted: 1/29/2010

Question Number: 3

On typical sections B for 600 and 300, if pavement repairs are done you will be into the brick pavers and possibly deeper then the 6" depth for pavement repairs (per sheet 10). How will the additional material be paid for?

**The repair will only be to the top of the block.**

Question Submitted: 2/18/2010

Question Number: 4

Plan sheet 80 indicates the use of Type 2 anchors to be placed in the deck edge for attachment of the Twin Steel Tube Railing Posts. Please review and issue an addendum if it is intended to change the anchors to Standard TST anchors in lieu of the Type 2 anchors indicated in the plans.

**See Addendum**

Question Submitted: 2/18/2010

Question Number: 5

Reference #'s 23 and 24 are listed per SF in the bid items, should they be per EA as listed in the plans? The standard construction drawings for curb ramps (BP 7.1) have several options, will we be permitted to use more than one type of curb ramp material on this project? No where in the specs or Standard Drawings does it state we have to use one kind of material. Will we be required to mitre the ADA ramps as shown on page 3/3 of BP 7.1?

**A 1. See addendum. A 2. Different approved material can be used throughout the project but the same material must be used at each curb ramp location. A 3. Page 3/3 of BP 7.1 will be enforced. Which states you may have to mitre.**

Question Submitted: 2/18/2010

Question Number: 6

Should items 23 and 24 be each items and not square foot?

**See Addendum**

Question Submitted: 2/22/2010

Question Number: 7

Per CMS 102.07 we are notifying you of an error in the plans. The general summary on plan sheet 13 for Ref. 35, Item 407 Tack Coat has carried forward 11,303 gal from sheet 15 and 1,611 gal from sheet 16, however, the grand total on sheet 13 shows only 2,714 gal. The 2,714 gal is listed in the proposal.

Question Submitted: 3/9/2010

Question Number: 8

A question was asked on 02/22/10 about an error in tack quantities for this project. Seeing that this sells on Thursday of this week, can we expect an answer on this pretty soon.

**See Addendum**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.