

Ohio Department of Transportation

Prebid Questions

Project No. 090278

Sale Date - 5/13/2009

Question Submitted: 5/4/2009

Question Number: 1

In regard to the existing concrete sealer on the bridges on this project. For surface preparation for new sealer to be applied the spec reads as follows: F. Surface Preparation. Remove dust, dirt, oil, wax, curing compounds, efflorescence, laitance, coatings and other foreign materials from surfaces to be sealed. While we understand that the department will refer to the spec., can you please clarify that "coatings" includes existing concrete sealer and that the department will require 100% removal of the existing sealer before new can be applied. Due to the extensive amount of existing sealer on one of the bridges on this project, it is important for us to clarify this in order to prepare our bid for this project. Thank You

Yes, coatings would include concrete sealers and it is to be removed under Item 512, Sealing of Concrete Surfaces (epoxy-urethane) in accordance with CMS 512.03.

Question Submitted: 5/7/2009

Question Number: 2

The proposal calls for 32" Portable Concrete Barrier (REF 41), The plans on sheet 28/110 under stage construction calls for "Portable Concrete Barrier, 32" Bridge Mounted (unanchored). Please Clarify.

Due to the fact that the portable concrete barrier, 32" Bridge Mounted barrier is unanchored, the Portable concrete barrier, 32" (ref 41) is acceptable.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.