

# Ohio Department of Transportation

## Prebid Questions

Project No. 053004

Sale Date - 12/14/2005

Question Submitted: 10/25/2005

Question Number: 1

We think this project should require rock Channel Protection on the slopes under the structure. We do not see this required in the scope of work. Is Rock Channel Protection required and if so is it included in one of the scopes of work?

**Rock channel protection is not required on the slopes under the structure.**

Question Submitted: 12/6/2005

Question Number: 2

Scope of work 10.6 requires the DBT to perform a detailed flood plain analysis for the waterway crossing. Other requirements of the scope of work state the existing spans and profile will remain the same. If the existing opening does not change why perform the flood plain analysis? If the analysis is required what is the responsibility of the DBT if the opening is not adequate?

**A detailed flood plain analysis is required on all bridge redeck and replacement projects, therefore it is required for this project. For this project, if the existing bridge opening is not adequate as determined in the detailed flood plain study then the additional work above and beyond the scope of services as written will be paid for as a change order.**

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.