

Ohio Department of Transportation

Prebid Questions

Project No. 053003

Sale Date - 12/2/2005

Question Submitted: 10/25/2005

Question Number: 1

We think this project should require rock channel protection on the slopes under the structure. We do not see this required in the scope of work. Is Rock Channel protection required and if so is it included in one of the scopes of work?

Rock channel protection is not required on the slopes under the structure.

Question Submitted: 10/26/2005

Question Number: 2

Scope of work 15.3.G. (substructure) does not call for any abutment modifications. Will it be necessary to remove the portion of the wing outside the existing approach slab to make a seat for the new full width approach? (see existing abutment detail) Will any abutment removal and/or modifications be needed to build the wider superstructure? (existing structure 40' o/o new 40' toe/toe parapet = 43'+/- o/o)

This is a Design Build Project. The Designer is required to perform the work as set forth in the Scope of Services. If it is required to make modifications to the abutments to achieve the work as described in the Scope of Services, then this work will be required to be performed.

Question Submitted: 11/21/2005

Question Number: 3

Q) WILL 'CLASS HP CONCRETE TESTING' BE REQUIRED FOR THIS PROJECT?

No, Class HP Concrete Testing will not be required for this project. Class HP Concrete Test Slab will be required.

All prospective bidders, subcontractors, suppliers, materialmen and all others who have an interest in these prebid questions and answers are advised that these items are being provided for informational purposes only and are not part of the bidding documents. If a question warrants a clarification, the Department will issue an addenda addressing the request for clarification to all plan holders. If the Department believes that the bidding documents adequately address the request, the contractor will be advised accordingly.