



ESTIMATED QUANTITIES								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN
832	30000		EACH	EROSION CONTROL				
202	11501		EACH	PORTION OF STRUCTURE REMOVED, AS PER PLAN (MAIN MEMBERS)				
202	11501		EACH	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (SECONDARY MEMBERS):				
512	10600		FT.	CONCRETE REPAIR BY EPOXY INJECTION				
513	10201		LBS.	STRUCTURAL STEEL MEMBERS LEVEL UP, AS PER PLAN				
513	95030		EACH	STRUCTURAL STEEL MISC., REPAIR OF DAMAGED MEMBERS, DRILLING				
513	95030		EACH	STRUCTURAL STEEL MISC., REPAIR OF DAMAGED MEMBERS, COPE HOLES				
513	95000		FEET	STRUCTURAL STEEL MISC., REPAIR OF DAMAGED MAIN MEMBER, COMPLETE PENETRATION WELDING				
513	95000		FEET	STRUCTURAL STEEL MISC., REPAIR OF DAMAGED MAIN OR SECONDARY MEMBER, FILLET WELDING				
514	20001		SO. FT.	FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER PLAN (ONE COAT)				
514	20001		SO. FT.	FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER PLAN (TWO COAT)				
514	20001		SO. FT.	FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER PLAN (THREE COAT)				
516	47001		LUMP	JACKING & TEMPORARY SUPPORT OF STRUCTURE, AS PER PLAN				
519	11100		SO. FT.	PATCHING CONCRETE STRUCTURES				
849	10000		LUMP	DAMAGE ASSESSMENT				
849	10500		LUMP	SURFACE PREPARATION				
849	10600		HOURS	REPAIRING DAMAGED MEMBERS BY GRINDING				
849	10700		LUMP	STRAIGHTENING DAMAGED MEMBERS				
614	11000		LUMP	MAINTAINING TRAFFIC				
614	11200		HOUR	LAW ENFORCEMENT OFFICER W/PATROL CAR				
624	10000		LUMP	MOBILIZATION				