



BILL OF MATERIAL-ONE SUPPORT

1	Cable Support Assembly	
1	U-bolt	1" φ x 6'-4 1/2"
1	Galvanized Cable	1" x 32'-0"
1	Concrete 1-5 1/2'	4.7 cu. ft.

BILL OF MATERIAL-ONE ANCHOR

1	Cable Anchor Assembly	
2	U-bolts	1" φ x 6'-4 1/2"
6	Galvanized Cable Clamps	1"
1	Galvanized Cable	1" x 10'-1"
1	Concrete 1-5 1/2'	14 cu. ft.

NOTE: Above Bill of Material gives 32' of excess cable for each stretch of rail between anchors.

The piers may be precast or poured in place.
 All surfaces of supports to be painted by manufacturer with one priming coat of red or blue lead paint governed by Item I-10 and Section 9.4 or 9.5 of the "Material Details."

All bolts to be dipped in paint just before using.
 All metal surfaces not galvanized to receive two field coats of white paint governed by Item I-10 and Section 9.3 of the "Material Details."
 Further details contained in General Specifications, Item I-7.

TYPE "H" GUARD RAIL
DEPARTMENT OF HIGHWAYS
OHIO

CONST. DRAW. NO. 119. MAY, 1928.

Approved: *RMB* Ch. Engr. Const. Date: 5/19/28